

ESTIMATE



FROM

RDND Roofing & Remodeling
LLC.
603-851-8025
RDNDRoofingRemodelingLLC@
gmail.com
Owner Richard Boisvert

BILL TO

Diane English
341 Intervale Rd
Canterbury, NH 03244
603-493-3919
Canterburytails59@gmail.com

ESTIMATE

114

ESTIMATE DATE

03/02/2026

DESCRIPTION

RDND Roofing & Remodeling LLC. will:

Dig down as far necessary below the rotted beam.
We will then put as many temporary supports as needed after jacking
up the main support beam.
Remove as far up as needed of the 6x6 rotted post.
Install a sonotube to fill the hole with concrete and allow the concrete to
cure for minimally 24 hours.
Once the concrete has set properly and we have made sure of that, we
will then install pressure treated 6x6 post and any necessary plates and
extra supports.
Remove the temporary posts allowing the building back down to where
it should be.
Put together any other things that may have been disassembled.
Help back fill if needed to complete the job.

AMOUNT

1,223.00

TOTAL

\$1,223.00

TERMS & CONDITIONS

Total Cost - \$1,223.00
Deposit - \$623.00
Remaining - \$600.00

Deposit is due upon signing of contract. Remaining is due upon completion of job.

Diane English

Richard Boisvert

